



15.00m Progress P/I
PLA 030208

60.00m Road Plan 862 1052
Paved Highway No 40
RD 8621052
427.53
16'14.05"

100m LEASE OFFSET

Low Area Thick Willows

L.S. 7

L.S. 2

16'14.30"

429.09'

16'14.05"

Fd.I.Mp. R22

Poplar & Spruce to 40c

15.00

20.00

Proposed Surface Location for: PROGRESS 7-25

EQUIPMENT LIST	
ITEM	DESCRIPTION
1	BU-400 -- WELLHEAD ENCLOSURE
2	BU-500 -- INJECTION BUILDING
3	BU-600 -- TRANSFER PUMP AND FILTER BUILDING
4	BU-700 -- PUMP BUILDING
5	S-800 -- 1000BBL PRODUCED WATER TANK
6	S-810 -- 1000BBL PRODUCED WATER TANK
7	S-820 -- 1000BBL PRODUCED WATER TANK
8	S-830 -- 1000BBL PRODUCED WATER TANK
9	S-990 -- 400BBL SKIM OIL TANK
10	S-900 -- H2S SCRUBBER
11	MCC BUILDING
12	SERVICE BOARD

1. GENERAL CONSTRUCTION NOTES APPLY TO COMPLETE DRAWING PACKAGE.
2. ALL DIMENSIONS ARE TO BE FIELD CONFIRMED PRIOR TO CONSTRUCTION.
3. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
4. FAINT DASHED LINES ARE SHOWN FOR REFERENCE.
5. ALL PIPING TO HAVE A MINIMUM COVER OF:
1200 - ON LEASE
1200 - OFF LEASE
6. ALL STEEL RISERS AND UNCOATED BURIED PIPING TO BE EXTERNALLY COATED WITH YJ OR EQUIVALENT, FOR CORROSION CONTROL. APPLICATION TO EXTEND 500mm ABOVE GRADE.
7. ALL BELOW GRADE PIPING TO BE INSULATED TO FIRST FITTING BELOW GRADE.
8. COORDINATE DATUM IS LOCATED IN SOUTH WEST CORNER OF LEASE.
9. ALL LEASE COORDINATES ALIGNED WITH PLANT NORTH.
10. LOCATION OF ALL EQUIPMENT AND UNDERGROUND LINES ARE APPROXIMATE AND ARE TO BE CONFIRMED BY SURVEY AND HYDROVAC AS REQUIRED.
11. ELECTRICAL CABLES TO BE BURIED ABOVE PIPELINE @ A DEPTH OF 900mm BELOW GRADE, WITH SAND COVERING AND CAUTION RIBBON 300mm BELOW GRADE

[illegible]

A=APPROVAL E=DEMOLITION H=HAZOP B=BID F=FABRICATION C=CONSTRUCTION D=AS-BUILT